



# LLRF system for the Fermilab PIP-II Superconducting LINAC

P. Varghese, B. Chase, S. Raman, Syed. A, P. Hanlet, D. Nicklaus, FNAL

L. Doolittle, S. Murthy, K. Penney, LBNL

C. Hovater, J. Latshaw, JLAB

23 October 2023

PIP-II is a partnership of:


- US-DOE
- India-DAE
- Italy-INFN
- UK-STFC-UKRI
- France-CEA, CNRS/IN2P3
- Poland-WUST, WUT, TUL

# Outline

1. PIP2-LINAC Accelerator Components
2. Physics Requirements – LLRF Specifications
3. LLRF Systems
  - a) RFQ
  - b) Bunchers 1-4
  - c) HWR Cryomodule
  - d) SSR1 Cryomodule
  - e) HB650 Cryomodule
3. LLRF Testing at CMTF and STC
4. EPICS User Interface
5. Results and system performance

# Fermilab Accelerator Complex

Fermilab Accelerator Complex



# PIP-II Superconducting RF CW Linac, 800 MeV Consists of Five Types of Cryomodules





**Elliptical**  
HB650 X 4  
24 Cavities  
650 MHz



**Single Spoke**  
SSR2 X 7  
35 Cavities  
325 MHz



177 MeV  
Superconducting



**Cryoplant**




**CDS**




**HWR**  
8 Cavities  
162.5 MHz



**Single Spoke**  
SSR1 X 2  
16 Cavities  
325 MHz



**H-Ion source**



**RFQ**

2.1 MeV  
Room Temperature

10 MeV

32 MeV

516 MeV

833 MeV


# PIP2-IT Accelerator Components

30 keV

2.1 MeV

10 MeV

22 MeV



Ion  
Source

RFQ, B1  
VXI Crate  
2 MFC cards

Buncher2,3

1 SOCMFC  
Chassis

HWR

4 SOCMFC

Chassis

1 Tuner

Signal Cond  
Module

SSR1

4 SOCMFC

Chassis

2 Resonance


Control Chassis

# PIP2 LLRF Systems


CM type	Cavities per CM	Number of CMs	CM configuration <sup>+</sup>	CM length (m)	$Q_0$ at 2K ( $10^{10}$ )	Surface resistance, (nΩ)	Loaded Q <sup>△</sup> ( $10^6$ )
HWR	8	1	8×(sc)	5.93	0.5	9.6 (2.75 <sup>†</sup> )	2.32
SSR1	8	2	4×(csc)	5.53	0.6	14 (10 <sup>‡</sup> )	3.02
SSR2	5	7	sccscsc	6.3*	0.8	14.4	5.05
LB650	4	9	cccc	5.52*	2.15	9.0	10.36
HB650	6	4	cccccc	9.92*	3	8.7	9.92

	Station 1	Station 2	Station 3	Station 4	Station 5	Station 6	Station 7	Station 8	Station 9	Station 10	Station 11	Total
	RFQ, B1-4	HWR	SSR1- 1,2	SSR2- 1,2,3	SSR2- 4,5	SSR2- 6,7	LB650- 1,2,3	LB650- 4,5,6	LB650- 7,8,9	HB650- 1,2	HB650- 3,4	
Number of cavities	6	8	16	15	10	10	12	12	12	12	12	125
RF Freq (MHz)	162.5	162.5	325	325	325	325	650	650	650	650	650	


S3 – SSR1-1,SSR1-2




S4-S11 – SSR2 (7),  
LB650 (9), HB650 (4)




# 4-cavity LLRF Station Rack – Components 1



LBL-Marble RFS  
Xilinx – Kintex



FNAL- LLRF Controller  
Intel – Arria10 SOC



# 4-cavity LLRF Station Rack – Components 2



1320 MHz Clock Distribution

LO Distribution

Reference Distribution

Dual Temperature Controller

8-Channel Downconverter

8-Channel Downconverter

4-Channel Upconverter

UC/DC Power Supply


LLRF Controller

LLRF Controller


Resonance Controller

RCC Power Supply


JLAB/FNAL  
Resonance Controller  
(Marble FPGA)  
Xilinx – Kintex




# PIP2 4-Cavity RF Station




# LLRF System Architecture 1 - Amp/Phs Control



# SEL System Architecture




# LLRF System Architecture 2 – I/Q Control




# Resonance Controller Architecture


Resonance Controller FPGA Block Diagram





# Resonance Control Processing




# HWR LLRF System with Pneumatic Tuner Control




# HWR Resonance Control Design



## Control System Model




## Control System Simulation



# HWR Control Performance


HWR Amplitude and Phase Regulation					
	Cavity4	Cavity5	Cavity6	Cavity7	Cavity8
<b>Cavity Field Setpoint (MV/m)</b>	2.89	6.04	8.94	8.5	8
<b>Amplitude Regulation (rms) %</b>	0.0135	0.0106	0.0101	0.0081	0.0103
<b>Phase Regulation (rms) deg</b>	0.0228	0.0065	0.0056	0.0055	0.0062
<b>Feedback Proportional Gain</b>	1000	1000	1000	1000	1000
<b>Feedback Integral Gain (rad/sec)</b>	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000

## Detuning Histograms



## PIP-II Specifications


- Energy Stability(Linac) < 0.01%
- Amplitude Regulation(individual cavity) < 0.06 rms %
- Phase Regulation < 0.06 rms deg
- Maximum detuning < 20 Hz




# RF Cavity Parameters and Feedback Gains

Cavity Type	$Q_L$	$f_0$ (MHz)	$f_H$ (Hz)	$K_P$	
Warm Cavity	3000	53	$8.83 \times 10^3$	15	
RFQ	15000	162.5	$5.542 \times 10^3$	23	Maximum Feedback
Buncher Cavity	10000	162.5	$8.125 \times 10^3$	16	Gains computed
HWR Cavity	$2.32 \times 10^6$	162.5	35	3548	for Stability with a
SSR1 Cavity	$3.02 \times 10^6$	325	53.8	2317	45 degree phase
SSR2 Cavity	$5.05 \times 10^6$	325	32.2	3846	Margin with 1 us
LB650 Cavity	$10.36 \times 10^6$	650	31.4	3935	Loop delay
HB650 Cavity	$9.92 \times 10^6$	650	32.76	3801	
LCLSII Cavity	$4 \times 10^7$	1300	16.25	7600	

$$\frac{C(s)}{R(s)} = \frac{K_P \omega_H (s + K_I/K_P)}{s^2 + s(K_P + 1)\omega_H + K_I\omega_H}$$




# SSR1 LLRF System with Piezo Tuner Control




# SSR1 Cryomodule Testing

SSR1 Amplitude and Phase Regulation								
	Cavity1	Cavity2	Cavity3	Cavity4	Cavity5	Cavity6	Cavity7	Cavity8
<b>Cavity Field Setpoint (MV/m)</b>	4.88	4.63	4.78	7.32	7.8	7.56	7.32	10
<b>Amplitude Regulation (rms) %</b>	0.0194	0.0289	0.0219	0.0157	0.014	0.0158	0.0147	0.0124
<b>Phase Regulation (rms) deg</b>	0.0116	0.0164	0.0118	0.0091	0.0088	0.0093	0.0092	0.0076
<b>Feedback Proportional Gain</b>	1600	1600	1600	1600	1600	1600	1600	1600
<b>Feedback Integral Gain (rad/sec)</b>	3,000,000	3,000,000	3,000,000	3,000,000	3,000,000	3,000,000	3,000,000	3,000,000


## Microphonics Detuning



## Piezo Transfer Function – C1



# RF Detune Calibration



$$\ddot{\mathbf{V}}(t) + \frac{\omega_0}{Q_L} \dot{\mathbf{V}}(t) + \omega_0^2 \mathbf{V}(t) = \frac{\omega_0 R_L}{Q_L} \dot{\mathbf{I}}(t)$$

$$\frac{d\vec{V}}{dt} = (-\omega_{1/2} + j\Delta\omega)\vec{V} + R_L\omega_{1/2}\vec{I}$$

$$\frac{d\vec{V}}{dt} = a\vec{V} + b\vec{K}_1$$

$$a = \frac{1}{\vec{M}_V} \cdot \left[ \frac{d\vec{M}_V}{dt} - \beta \vec{M}_K \right]$$

- The cavity is operated in pulse mode with a cavity field  $\sim 1/2$  FS magnitude and the cavity probe and forward waveforms are recorded.
- Numerical analysis of the acquired data provides cavity parameters such as half bandwidth and the detuning constants


# Cavity Quench Detection/ Overdrive Protection

$$P_{\text{diss}} = |\vec{K}|^2 - |\vec{R}|^2 - \frac{dU}{dt}$$

$$U = \frac{V^2}{\omega_0(R/Q)}$$

$$\frac{dU}{dt} = 2\Re \left( \vec{V} \frac{d\vec{V}}{dt} \right) \cdot \frac{1}{\omega_0(R/Q)}$$

$$f_K |\vec{M}_K|^2 - f_R |\vec{M}_R|^2 - f_V 2\Re \left( \vec{M}_V \cdot \frac{d\vec{M}_V}{dt} \right) - f_Q$$



- Quench Detection is based on computing the dissipated power in the cavity. The dissipated power is compared against a threshold for quench detection
- RF overdrive is detected when the controller output saturation persists beyond a specified time ( $\sim 1$  sec)

# HB650 and LB650 Cavity Testing at STC

- HB650, beta=0.9, **B9A-AES-001**
- January-March 2020
- STC commissioning for 650 MHz operations
- Prototype coupler/tuner validation/testing
- Prototype cavity characterization

- HB650, beta=0.92, **B92D-RRCAT-502**
- October-November 2021
- Prototype coupler/tuner validation/testing
- Prototype cavity characterization, qualification for prototype HB650 cryomodule assembly

- LB650, beta=0.61, **B61-EZ-001**
- June -September 2022
- Preproduction coupler/tuner testing
- Prototype cavity characterization



Bare HB650 Cavity



LB650 Cavity on ANL EP stand


# LB650 Cavity Measurements





$4/5\pi$  Mode, 625 kHz




$3/5\pi$  Mode, 2.125 MHz



Suppression with notch filters



LFD Coefficient = 2.4




Detuning Spectrogram


# HB650 Cavity Measurements




GDR Mode 15 MV/m




Piezo Tuner Controls




Tuner Waveforms



$$df/dp = 6.0 \text{ Hz/Torr}$$



$$\text{LFD Coefficient} = 1.6$$




Piezo Transfer Function

# Prototype HB650 Cryomodule Testing at CMTF




pHB650 Cryomodule




SSA Non-linearity



40 kW SSA





SSA Calibration



SELAP Mode at 7 MV/m


# Prototype HB650 Cryomodule Testing at CMTF




## Piezo Waveforms

## GDR Mode at 5MV/m

# User Interfaces



Labview



EPICS

```

PA P30 LLRF/HPRF Control<NoSets><DPM-DPM03 (1%)>
SET D/A A/D Com-U Pgm-Tools
P30 SSR1 CAVITY5 CALIBRATIONS
-<FTP>+ *SA* X-A/D X=TIME Y=Z:NFMOM ,Z:NFDOUT ,Z:NXMDAT,Z:NPCALC
COMMAND ---- Eng-U I= 0 I= 0, 2807000, 0, 2807000
-<14>+ r-e6 AUTO F=.1 F= 2809000, 2809000, 250, 2809000
...hur ...SSR1 global .....
! CAVITY 5 !
! DOWNCONVERTER CALIBRATIONS !
-P:SS5CDCMG C5 CAV DC Mag 1 1 0-1
-P:SS5CDCPH C5 CAV DC Phase -37 -37 deg
-P:SS5FDCMG C5 FWD DC Mag 1 1 0-1
-P:SS5FDCMP C5 FWD DC Phase -87.5 -87.5 deg
-P:SS5RDCMG C5 REV DC Mag 1 1 0-1
-P:SS5ROCPH C5 REV DC Phase -115.5 -115.5 deg
-P:SS5RFOCM C5 REF DC Mag 1 1 0-1
-P:SS5RFOPC C5 REF DC Phase 0 0 deg
! UNIT CALIBRATIONS !
-P:SS5CSTMV C5 CAV Scl to MV 3.6099999 3.6099999
-P:SS5CSTSQ C5 CAV Scl to Sqrt(w) 1 1
-P:SS5CLEN C5 CAV Length .205 .205 m
-P:SS5FSTSQ C5 FWD Scl to Sqrt(w) 1.626 1.626
-P:SS5RSSTSQ C5 REV Scl to Sqrt(w) 1.65 1.65
-P:SS5FTTH2 C5 Freq Trk Off to Hz -.36219999 -.36219999
-P:SS5CAVQL C5 Cavity QL 40000000 40000000

! AVERAGING WINDOWS !
-P:SS5CAVST C5 CAV Avg Gate Start 1000 1000 us
-P:SS5CAVM0 C5 CAV Avg Gate Width 1000 1000 us
-P:SS5FAVST C5 FWD Avg Gate Start 1000 1000 us
-P:SS5FAVMD C5 FWD Avg Gate Width 1000 1000 us
-P:SS5RAVST C5 REV Avg Gate Start 1000 1000 us
-P:SS5RAVMD C5 REV Avg Gate Width 1000 1000 us

! SCALAR READBACKS !
P:SS5CAVMG C5 CAV Mag *.0012369 MV/m
P:SS5CAVPH C5 CAV Phase -10.024692 deg
P:SS5CAVPP C5 CAV Probe Pow 0 kWatt
P:SS5FWMG C5 FWD Pow Mag .00000004 kW
P:SS5FWPH C5 FWD Pow Phase 3.1749876 deg
P:SS5RVMG C5 REV Pow Mag .00000006 kW
P:SS5RVPH C5 REV Pow Phase 17.323978 deg
P:SS5CAVFT C5 CAV Freq Tracking .72439998 Hz
P:SS5RESER C5 Resonance Freq Error -2 Hz

```





ACNET

# Summary




- PIP-II LLRF System is in the Final Design Review Stage
- The design is closely aligned with the LCLS-II LLRF system
- Various hardware/software components have been tested at PIP2-IT and STC
- The LLRF systems at PIP2-IT met the project requirements
- All the different cavity types(7) have been tested with the LLRF system
- Final design prototypes will continue to be tested at both facilities
- The EPICS user interface has been used in the test stands
- The Final Design Review is expected in early 2024

# Thank You!


# RFQ and B1 LLRF System




# Beam Loading Compensation – B2



# $Q_L$ Measurement



HWR Cavity 5,  $Q_L = 2.07e6$



SSR1 Cavity 5,  $Q_L = 4.11e6$

