# **Korea-4GSR Accelerator Overview**



Jaehyun Kim

On behalf of Korea-4GSR Beam Dynamics Group Pohang Accelerator Laboratory, POSTECH

April 17, 2024







## **4GSR Outline**

## Multipurpose Synchrotron Radiation Construction Project

- Period: 2021 July to 2027 June (6yrs)
- Budget: 1.0454 Trillion KRW (≈ USD 750M)
- Land: 540,000 m<sup>2</sup> / Building: 69,400 m<sup>2</sup>
- Location: Ochang, Chungcheongbuk-do

### **Specifications**

- Beam Energy: 4 GeV
- Beam Emittance: less than 100 pm·rad (TDR: 62 pm·rad)
- Circumference: 800m
- Beamlines : more than 40
- Accelerator: Gun, Injector LINAC, 4 GeV Booster
- Lattice: Hybrid 7 Bend Achromat (H7BA)



1



### **Design Features of Korea-4GSR**

### **\*** High photon beam performance from storage ring


- The best performance in the range of 10 30 keV
- Capability to generate photon beam up to 100 keV

## Considering well demonstrated technologies for the design

- Off-axis injection with conventional injection scheme
- General technologies for magnet and vacuum systems
- On schedule user service and full performance

## Synergy with PLS-II and PAL-XFEL

- Supporting full range of synchrotron radiation application





### **Brilliance Curves**

#### 1.E+22 1.E+20 1.E+18 1.E+16 1.E+14 1.E+12 Brilliance 1.E+10 BM EPU98 1.E+08 IVU24 **U20** 1.E+06 VU20(PLS-II) 1000 10000 100000 10 100 Photon Energy [eV]

**Brilliance vs photon Energy** 

- 4 GeV electron beam energy is chosen for best performance of photon beam in the range of 10 - 30 keV
- ~100 times brighter photon beam than that of PLS-II

3



## **Beamlines**


	Beamline
Industry oriented	1 BioPharma BioSAXS
	2 Material Structure Analysis
	③ Soft X-ray Nano-probe
Research oriented	(4) Nanoscale Angle-resolved Photoemission Spectroscopy
	5 Coherent X-ray Diffraction
	6 Coherent Small-angle X-ray Scattering
	⑦ Real-time X-ray Absorption Fine Structure
	8 Bio Nano Crystallography
	9 High Energy Microscopy
	10 Nano-probe





#### **Storage Ring Lattice Parameters**

Parameters	Value
Energy (GeV)	4.0
Circumference (m)	799.297
Emittance (pm)	62
Tunes (H,V)	68.18, 23.26
Natural chromaticity (H,V)	-112.1, -85.3
Chromaticity (corrected) (H,V)	5.8 , 3.5
Hor. Damping partition	1.84
Momentum compaction	$0.78 imes10^{-4}$
Energy spread ( $\sigma_{\delta}$ )	$1.26  imes \mathbf{10^{-3}}$
Energy loss per turn (MeV)	1.097
Main RF voltage (MV)	3.5
Beam current (mA)	400
Bunch length ( <i>σ<sub>z</sub></i> ) (mm) (w/o HC, w/ HC)	3.66 / 14.66




#### Normalized emittance vs. circumference for 3GSRs and 4GSRs



#### **2024 Spring EPICS Collaboration Meeting**

### **Linear Optics**




### Unit cell


- The storage ring is a 800 m 4 GeV 28-cell ring with natural emittance of 62 pm
- The unit cell is a H7BA with 2-T center bend •
- The ring is composed of 28 H7BA cells (28 identical arcs, 26 ID SS + 2 high-beta SS)
- Phase advance is matched (  $\Delta \phi_{x,A} = \Delta \phi_{x,B}$  and  $\Delta \phi_{y,A} = \Delta \phi_{y,B}$  ) •
- Though the ring has 2-fold geometric symmetry, it has 28-cell symmetry in terms of on-momentum phase advance
- One high-beta straight is dedicated for off-axis injection •




**Nonlinear Dynamics** 



**ELERATOR LABORATORY** 




# Amplitude dependent



### **Error Tolerance**

Magnet	Misalignment (µm) (X/Y/Z)	Rotation (µrad) (Roll/Pitch/Yaw)	Strength error (%)
LGBM	30 / 30 / 250	400 / 100 / 100	0.05
Combined- function magnet	30 / 30 / 250	400 / 100 / 100	0.05
Quadrupole	30 / 30 / 250	400 / 700 / 700	0.05
Center bend	30 / 30 / 250	400 / 100 / 100	0.05
Sextupole	30 / 30 / 250	400 / 700 / 700	0.05
Octupole	30 / 30 / 250	400 / 700 / 700	0.05
Girder	100 / 100 / 100	400 / - / -	



### Example of horizontal offset distribution over reference orbit

Overall offset = girder offset + magnet offset w.r.t girder


#### Magnet error

Offset (µm) (X/Y)	Roll (µrad)	Calibration error (%) (X/Y)
500 / 500	100	5 / 5

#### **BPM** error



**Dynamic Aperture and Momentum Aperture** 



-Results with 50 random error seeds -Realistic correction chain (orbit correction, LOCO, etc) is applied for each seed


- a single bunch of 1 nC (or 0.375 mA) 400 mA = 1067×0.375 mA Coupling ratio (emity/emitx) = 0.10



## Impedance Budget


Bunch length	14 mm				
Element	Number	Loss factor (V/pC)	Hor. Kick factor (V/pC/m)	Ver. Kick factor (V/pC/m)	Remarks
Resistive wall	1	2.385	-1429.018	-7504.161	All IDs are closed
BPM	288	0.001	-1.548	0.237	
Bellows	750	0.000	-0.261	-0.321	
Flange	600	0.000	-0.083	-0.191	
Mask	84	0.000	0.000	0.000	
Gate valve	56	0.096	-6.730	-42.916	
Pumping tee	28	0.004	-10.771	2.226	
Main RF cavity	12	0.199	-2.090	-2.090	
LFB	2	0.240	-20.575	-22.173	Longitudinal feedback
TFB	2	0.027	1.343	-8.406	Transverse feedback
Sum		11.083	-2862.404	-10218.569	

\*Impedance of ID section is in progress \*No HHC design yet





#### Linac




## **LCW** parameters

- Acceleration tube :  $28 \pm 2^{\circ}C$  (~50 kHz/ °C)
- Photocathode gun: 25 ~ 50 °C



#### **2024 Spring EPICS Collaboration Meeting**






773 m	Booster	Value	Unit
	Circumference	772.893	m
	Beam Energy (Inj Ext.)	0.2 - 4	GeV
	Cell number	60	
Design Parameters	Natural Emittance at 4 GeV	7886	pm ra
	Natural Emittance at 200 MeV	20	pm ra
	Momentum Compaction	0.000933	
	Horizontal Tune	19.226	-
	Vertical Tune	13.165	-
Tune and Chromaticity	Natural Horizontal Chromaticity	-27.1	-
	Natural Vertical Chromaticity	-18.2	-
	Horizontal Chromaticity	2	(targe
	Vertical Chromaticity	2	(targe
	Energy Loss per Turn	1671.3	keV
	Energy Spread	0.106	%
Radiation related	Horizontal Damping Time	8.5	ms
	Vertical Damping Time	12.3	ms
quantities	Longitudinal Damping Time	8.0	ms
at 4GeV	Synchrotron Frequency	4235	Hz
	Synchrotron Tune	0.0109	
	Bunch Length	11.1	mm

POHANG ACCELERATOR LABORATORY

**Booster Beam Dynamics** 




Evolution of emittance and energy spread during energy ramping

Y. Lee et al., Nuclear Instruments and Methods in Physics Research A 1060 (2024) 169074



## **Injection to Storage Ring (4-Kicker Bump)**



### Booster-to-Storage ring beam transport line



## **Beam Diagnostics Summary**


## Types, Numbers & Locations (2023-Oct-24)


CODE	Ture a	Maga Tarrat	Numbers / Section				
CODE	CODE Type Meas. Target		LINAC	LTB	BR	BTS	SR
1	BPM (BTN, STRL*)	Beam Position	10	7	120	6	288
2	BPRM (YAG/OTR)	2D Profile, Emittance, Energy	7	7		3	
3	X-ray Diagnostic Hutch	Beam Size, Emittance, Energy Spread					1
4	Visible light Diagnostic Hutch	Beam Size, Emittance, Bunch Length & Purity			1		3
5	Beam Loss Monitor(FAST-PMT)	Beam Loss			5		30
6	Beam Loss Monitor(SLOW-Scintillating Fiber)	Beam Loss	1	1	4	1	14
7	ICT	Pulse Beam Current	2	1		2	
8	DCCT	DC Beam Current			1		2
9	FCT	Filling Pattern			1		1
10	PBPM	Photon Beam Position					30
11	Tune Monitor	Tune			1		1
12	Faraday Cup	Beam Current	1				
13	TFS/LFS	Multi-bunch Feedback					2
	Numbers in total		21	16	133	12	370
		15		PA	POHANG	G ACCELERAT(	OR LABORATO

### **Storage Ring Beam Diagnostics Summary**

## **Storage ring beam diagnostics**

- Beam Position: Button BPM x 280+8 (28+2 periodic cell) ٠
- Beam Size, Emittance, Bunch Length & Purity • :Visible light Diagnostic Hutch x 3
- Beam Size, Emittance, Energy Spread ٠ :X-ray Diagnostic Hutch x 1
- Beam Loss: Slow BLM x 7 module, Fast BLM x 28 ٠
- Beam Current : DCCT x 2 ٠
- Filling Pattern : FCT x1 ٠
- Tune: Tune monitor x 1 ٠
- Photon beam position : PBPM x 30 ٠
- Bunch-by-bunch Feedback: TFS x 1, LFS x1 ٠
- PBPM Feedback\*: Invar BPM x 4 (TBD) ٠






Diag. Hutch location: VDH (3+1), XDH 1




### **Storage Ring BPM system Summary**

## **4GSR Button BPM**

- Two type of buttons were designed ٠
  - RF design was finished and under prototyping
    - Alumina Ceramic / Borosilicate Glass
  - Antenna design that meets the both operation conditions of w/ & w/o 3rd harmonic cavity
  - Temp. sensor & fiducial mark will be placed on BPM chamber
  - All BPM will be used button pick-up (Linac. to SR)







Type-B (Al<sub>2</sub>O<sub>3</sub> Alumina)



## **4GSR BPM electronics**

- Proto-type BPM electronics was tested @ PLS-II
- SR BPM electronics requirement
  - Turn by turn beam position @ 375kHz with 1um
  - Fast beam position @ 10kHz with 200 nm
  - Slow beam position @ 10Hz with 10 nm
  - Bunch-by-bunch monitoring also possible






nnel ADC Module X 4 slo




POHANG ACCELERATOR LABORATORY


#### **2024 Spring EPICS Collaboration Meeting**






#### **Booster Magnet Status Summary**







Combined Bending Magnet (60EA, Procurement Plan: 2/2 of 2023)



Quadupole (66EA, Procurement Plan: 2/2 of 2023)




Sextupole (60EA, Procurement Plan: 2/2 of 2023)




Corrector (240EA, Procurement Plan: 2/2 of 2023)

## POHANG ACCELERATOR LABORATORY









LGBM2 (56EA, On Manufacturing: 1/2 of 2023~) LGBM1 (56EA, Procurement Plan: 2/2 of 2023)

**2T Center Bend** (28EA, On Manufacturing: 1/2 of 2023~)



DQ (224EA, Procurement Plan: 2/2 of 2023)



#### Quadrupole Magnet (344EA, Procurement Plan: 2/2 of 2023)

## (56EA, Procurement Plan: 2/2 of 2023)




#### Selection of RF system

#### Storage Ring RF System(10 RF Stations)

- Cavity : EU HOM Damped Normal Conducting Cavity ٠
- HPRF: 150 kW SSPA
- LLRF : Pizza box type ٠
- RF Transmission : WR1800 Waveguide ٠

### Booster Ring RF System(3 RF Stations)

- Cavity : 5-cell PETRA Normal Conducting Cavity
- HPRF: 80 kW SSPA
- LLRF : Pizza box type
- RF Transmission : WR1800 Waveguide



#### **Operating Specification** Resonant frequency **Operating Temperature** Tuning range of plunger Quality factor Q<sub>0</sub> Coupli Coupling beta (adjustab Shunt impedance Rsh=l Length (flange-flange) Typical input c.w. powe Max. input c.w. power Acc. Voltage at 60kW Operating temperature Coupler Cooling air ove Cooling air flow Water pressure Pressure drop Water flow Vacuum Leak Rate


< 5-cell PETRA Cavity for BR>


Parameter	Unit	Values	Remark
Beam current	mA	400	
Revolution frequency	MHz	0.37528	
Harmonic number	-	1332	
RF frequency	MHz	499.594	
Electron energy loss /turn by bending magnet	keV	1097.65	
Electron energy loss /turn by IDs	keV	720.00	
Electron energy loss /turn by Others (estimated)	keV	60.00	loss by vacuum chamber
Total beam energy loss /turn by turn	keV	1877.65	

Unit	Value
MHz	499.594
MOhm	3.4
-	> 29,000
-	1~6
kW	120
kV	700
°C	25
l/m	143
mbar I/s	< 2e-10

1			
	MHz	499.8	
e range	°C	3040	
rs	MHz	1	
ing beta		>29 000	
ole)		1.0 -3.0	
U²/(2Pin)	MΩ	15	
	m	1.650	
er	kW	60	
	kW	120	
	MV	1.3	
e (typ.)	°C	30	
rpressure	mbar	>10	
	m³/hour	23	
	bar	10	
	bar	6	
	l/min	150	
	mbarl/s	<1e-10	







#### **Vacuum Status Summary**

- **Design status**
- 3D modeling completed •
- Vacuum profile calculation completed • (Average pressure = 1E-9 mbar)
- Thermal analysis of photon absorbers completed ٠
- Design of insertion device vacuum chambers underway ٠
- Design optimization within 2023 ٠

#### Purchase and fabrication plan

- Completion of manufacturing drawing: ~ 1/2 of 2024 ٠
- Vacuum chambers prototype: ~ 1/2 of 2024 ٠
- Purchase order of vacuum chambers: 2/2 of 2024 ٠
- Purchase order of commercial components : 2025 ٠
- Assembly and vacuum test: 2025 ~ ٠

#### Vacuum chamber prototype

**Extruded Aluminum chamber (CH12)** 










Machined aluminum chamber(CH02)



 $< \pm 50 \ \mu m (X)$  $< \pm 50 \, \mu m (Y)$  $< \pm 20 \,\mu m (Z)$ 







% error < ±0.5 mm







3 Weldi





POHANG ACCELERATOR LABORATORY

### Summary

## Multipurpose Synchrotron Radiation Project

- The project aims to build 4 GeV storage ring with an emittance less than 100 pm
- Its circumference is 800 m
- It can host more than 40 beamlines. Initially, 10 beamlines will be ready

## 2 institutions working together

- KBSI: Leading institution in charge of building and facility
- PAL: Partner institution in charge of Accelerator and beamlines

## Construction will be completed by 2027

- TDR has been finished
- Construction will be started in spring, 2024



# Thank you for your attention



